

Republic of the Philippines

Department of Education

BIDS AND AWARDS COMMITTEE I

SUBJECT

BID BULLETIN NO. 3

PROJECT

Supply, Delivery, and Installation of Modular Tables,

Chairs, and Mobile Cabinets for DepEd CO Staff

PROJECT NO .:

2024-AdmS2(004)-BI-CB-041

DATE

November 11, 2024

This Bid Bulletin is hereby issued for the information and guidance of all prospective bidders. It shall form an integral part of the bidding documents issued earlier relative to the above project.

I. Section V. Special Conditions of Contract

GCC clause 2.2, on pages 30 to 31, of the bidding documents is hereby amended to read:

Original	Provision as Amended
Timelines	Timelines
First delivery and installation of one hundred (100) sets/units/pieces within thirty (30) calendar days upon receipt of Notice to Proceed (NTP).	First delivery and installation of one hundred (100) sets/units/pieces within sixty (60) calendar days upon receipt of Notice to Proceed (NTP).
Second delivery and installation of one hundred (100) sets/units/pieces from Day 31 to Day 60.	Second delivery and installation of one hundred (100) sets/units/pieces from <u>Day 61 to Day 90.</u>
Third delivery and installation of one hundred (110) sets/units/pieces from Day 61 to Day 90.	Third delivery and installation of one hundred (110) sets/units/pieces from Day 91 to Day 120.

Section VI. Schedule of Requirements: II.

Item A List/Description of Goods/Services, on page 35, of the bidding documents is hereby amended to read:





Room M-512, 5th Floor, Mabini Building DepEd Complex, Meralco Avenue, Pasig City 1600 Telephone No.: (02) 8633-9343; 8637-8292

Doc. Ref. Code | ProcMS-BACSD-F002 | Rev | 00 Effectivity 01.09-23 Page 1 of 3

Page 1 of 3

Original	Provision as Amended
Delivery Period	Delivery Period
First delivery and installation of one hundred (100) sets/units/pieces within thirty (30) calendar days upon receipt of Notice to Proceed (NTP).	First delivery and installation of one hundred (100) sets/units/pieces within sixty (60) calendar days upon receipt of Notice to Proceed (NTP).
Second delivery and installation of one hundred (100) sets/units/pieces from Day 31 to Day 60.	Second delivery and installation of one hundred ten (100) sets/units/pieces from <i>Day 61 to Day 90</i> .
Third delivery and installation of one hundred ten (110) sets/units/pieces from Day 61 to Day 90.	Third delivery and installation of one hundred ten (110) sets/units/pieces from Day 91 to Day 120.

• **Item B Contract Duration**, on page 35, of the bidding documents is hereby amended to read:

Original		Provision as Amended
Complete delivery shall	be made	Complete delivery shall be made One
Ninety (90) calendar days u	pon receipt	Hundred Twenty (120) calendar days
of NTP	_	upon receipt of NTP

III. Section VII. Technical Specifications:

• **Item No. 1,** on pages 38 to 39, of the bidding documents is hereby amended to read:

Original	Provision as Amended
Modular Tables (Set)	Modular Tables (Set)
a. Table	a. Table
Work Area Measurement: 1.50m x	Work Area Measurement: 1.50m x
2.00m	2.00m
Table Top: The tabletop shall be made	Table Top: The tabletop shall be made
of 25mm thick high-pressure laminate	of 25mm thick high-pressure laminate
(HPL) with slide-out keyboard tray	(HPL) with slide-out keyboard tray
Tabletop Dimension: 1.20m (L) x	Tabletop Dimension: 1.20m (L) x 0.60m
0.60m (W) x 0.75m (H) with +/- 5mm	(W) x 0.75m (H) with +/- 5mm
tolerance	tolerance
With built in desk wire hole	With built in desk wire hole
Desk Wire Hole Size: 70mm Diameter	Desk Wire Hole Size: 60mm-70mm
(with grommets or cover)"	Diameter (with grommets or cover)"
Keyboard Tray Dimension: 0.30m	Keyboard Tray Dimension: 0.30m
(depth) x 0.50m (length)	(depth) x 0.50m (length)
b. Cubicle Partition	b. Cubicle Partition
b. Capital Latitudi	S. Sastos I at titon
Type of Partition: Low Partition (1.0m)	Type of Partition: Low Partition (1.0m)
with glass (0.25m)	with glass (0.25m)



Page 2 of 3

1.0 Frames:
Monolithic modular partition with tiled appearance.

Frames is extrude aluminum with noncorrosive type of paint (powder coated finish/charcoal gray) with 60mm thickness

Frame tiles backing or core made of steel and maple wood grain finish

Monolithic modular partition with tiled appearance.

Glass frames size is gauge 18 with 60mm thick and glass tiles is clear glass with 1/4 thickness

1.1 Strips (Edging): Maple Wood Grain Finish

1.0 Frames:

Monolithic modular partition with tiled appearance.

Frames is extrude aluminum with noncorrosive type of paint (powder coated finish/charcoal gray) with 60mm thickness

Frame tiles backing or core made of steel and maple wood grain finish

Single monolithic modular partition with tiled appearance.

Glass frames size is gauge 18 with 60mm thick and glass tiles is clear glass with 1/4 thickness

1.1 Strips (Edging): Maple Wood Grain Finish

• Item No. 2, on page 39, of the bidding documents is hereby amended to read:

Original	Provision as Amended
Chairs	Chairs
Fabric upholstered back and seat (black color)	Fabric upholstered back and seat (black color)
300 nylon base and nylon casters/ tilt lock mechanism/swivel function/ load capacity of 80 kgs.	300 <u>chrome</u> base and nylon casters/ tilt lock mechanism/ swivel function/ load capacity of 80 kgs.
Dimension: 57cm (L) x 46cm (W) x 92-100cm (H)	Dimension: 57cm (L) x 46cm (W) x 92-100cm (H)

• ANNEX "B" Design layout/drawing sample, on page 39, of the bidding documents is hereby amended to read:

Original	Provision as Amended
Display of Cubicle Partition	Display of Cubicle Partition
3/6 inches thick glass with frosted portion	Glass frames size is gauge 18 with 60mm thick and glass tiles is clear with 1/4 thickness

All other provisions not herein modified shall remain in full force and effect.

FOR THE BIDS AND AWARDS COMMITTEE I:

ALMA RUBY C. TORIO

Assistant Secretary and Chairperson

RON – LAR – EFB – SLA

Page 3 of 3